

Landscape, Arboricultural & Ecological Solutions for the Built Environment

> Arboricultural Impact Assessment

Meliden Road Dyserth Phase 2 LL18 6BP

Ref: P.1318.20

April 2020

Ascerta

Mere One, Mere Grange, Elton Head Road, St Helens WA9 5GG T: 0845 463 4404 F: 0845 463 4405 E: info@landscapetreesecology.com www.landscapetreesecology.com

P.1318.20

Arboricultural Impact Assessment

Meliden Road Dyserth Phase 2 LI18 6BP

For

Macbryde Homes

23rd April 2020

Field Work by	Robert Armitage BSc (Hons) MArborA
Document Author	Robert Armitage BSc (Hons) MArborA
Technical Review	Alistair McLeod
QA Review & Approval	Ciaran Power - Office Manager

Contents

Page

Introduction	3 -
Planning Policy & Relevant Legislation	3 -
Survey & Survey Methodology	4 -
Potential Arboricultural Impacts	5 -
Tree Protection Measures 6	6 -
Conclusions & Recommendations	7 -
References 8	8 -
	Introduction

Appendix 1	Tree Data Tables in accordance with Table 1 of BS5837: 2012
Appendix 2	Drawing P. 1318.20.01 <i>Tree Survey and Tree Removal Plan</i> Drawing P. 1318.20.02 <i>Tree Protection Measures</i>

1.0 Introduction

- **1.1** Ascerta has been instructed to carry out a survey of the trees within and immediately adjacent Meliden Road, Dyserth, Phase 2 and to assess the potential impact of the development as proposed on trees within / adjacent the site in accordance with British Standard 5837: 2012 *Trees in relation to design, demolition and construction Recommendations.*
- **1.2** The site was visited on 21st April 2020 by Robert Armitage, a competent and qualified arboriculturist with experience of the UK and European arboricultural and landscape industries within the context of the planning system. During the site visit, a survey was carried out of the trees growing both on and immediately adjacent the site to the standards contained within BS5837: 2012.
- **1.3** This report presents the results of the survey, provides an assessment of the impact of the development and includes recommendations for further actions, where applicable, to mitigate any potentially negative effects of the development on tree cover within the local landscape.
- **1.4** Our client's objective is to develop the site by the construction of thirty-three residential dwellings.

2.0 Planning Policy & Relevant Legislation

- **3.3** The site lies within the Denbighshire County Council administrative area and is subject to the policies contained within its Local Plan. These have been taken into account when writing this report.
- **3.4** Checks made with the Local Planning Authority on 23rd April 2020 via the council's online interactive map indicate that none of the trees within the site are subject to any Tree Preservation Orders and the site is not located within a Conservation Area. In advance of the commencement of any works to trees within or adjacent the site, those instructing and proposing to carry out such works should satisfy themselves that all appropriate consents are in place to prevent potential breach of legislation.
- **2.3** British Standard 5837: 2012 *Trees in relation to design, demolition and construction Recommendations* provides current recommendations and guidance on the relationship between trees and design, demolition and the construction processes. It sets out the principles and procedures to be applied to achieve a harmonious and sustainable relationship between trees and structures.

- **2.4** Consideration should also be given to any impacts from the proposed development in respect of the Hedgerow Regulations 1997 and the Forestry Act 1967 (and specifically the potential need for a felling licence), as well as existing UK and European legislation relating to wildlife and nature conservation.
- **2.5** In accordance with the Hedgerow Regulations 1997, 'important' hedgerows (in the context of the Regulations) should not be removed without a Hedgerow Removal Notice issued by the relevant Local Authority, unless that removal is subject to an appropriate consent under the Town and Country Planning Act 1990. Appropriate checks should be made in advance of the commencement of works to hedgerows to establish the importance or otherwise of the hedgerow and whether there is a requirement for a Hedgerow Removal Notice distinct from any formal planning consent to be granted.
- **2.6** The revised National Planning Policy Framework, updated on 19th February 2019, sets out the government's planning policies for England and Wales and how these are expected to be applied and has been considered within this report. It provides a Framework within which locally prepared plans for housing and other development can be designed and produced.

3.0 Survey & Survey Methodology

- **3.1** We have been supplied with a digital copy of the topographical survey map for the site, which satisfies the relevant part of section 4.2 of BS5837: 2012. Features of arboricultural or landscape interest that have been excluded from the original plan (for example trees on or located off site but within a distance from the boundary of the site equal to or less than 12 times the stem diameter of that tree) have been added to the plan manually.
- **3.2** Eleven individual trees, five groups of trees and five hedges were originally recorded as part of the wider site including Phase 1; however, this phase of the development (Phase 2) only contains three individual trees (T6, T7 and T8), three groups of trees (G4, G5 and G6) and two hedges (H1 and H2), the details of which can be found within Appendix 1 to this report and cross referenced with drawing P.1318.20.01 *Tree Survey and Tree Removal Plan.* For reference, G6 of this survey is an additional group of trees not included within the original tree survey including Phase 1.
- **3.3** Our original survey of the trees, including those contained with Phase 1 of the wider development, was carried out by a qualified and competent arboriculturist in accordance with sections 4.4 and 4.5 of BS5837: 2012 on 25th January 2018. Trees located within and immediately adjacent the Phase 2 site have subsequently been re-surveyed on 21st April 2020 to support this application. Trees surveyed have been numbered sequentially and the details required by the Standard, including a categorisation in accordance with section 4.5 and Table 1 of the Standard, have been recorded within the Tree Data Tables at Appendix 1.
- **3.4** Where trees are surveyed that require immediate attention, for example to abate a nuisance, prevent a serious hazard to life or property, or are affected by a pathogen or pest that could cause widespread damage unless it is controlled, notification will be issued to the relevant person or organisation such that appropriate action can be taken.

4.0 Potential Arboricultural Impacts

4.1 Table 1 below shows the trees that will need to be removed as part of the development of the site.

Tahla	1.	Troos	to h	a Pamovad
rable	11	rrees	to p	e Removea

<u>T. No.</u>	<u>Species</u>	<u>HT (m)</u>	<u>Stem</u> DBH	<u>Cat</u>	<u>Reason</u>
			<u>(mm)</u>	<u>Grade</u>	
G6	Blackthorn, Hawthorn, Sycamore, Elder and Holly	2-10	350+ 350	C2	To accommodate the development proposal.

4.2 Table 2 below shows trees that are proposed for retention within the development that have the potential to be negatively impacted by the development proposals.

Table 2: Summary of Potentia	I Impacts to Retained Trees
------------------------------	-----------------------------

<u>T. No.</u>	<u>Species</u>	<u>HT (m)</u>	<u>Stem</u> DBH	<u>Cat</u>	Potential Impact
			<u>(mm)</u>	<u>Grade</u>	
H1	Hawthorn and Elder	3.5	120 # average	B2	
G4	Ash, Sycamore and Cypress.	14	560	B2/C2	General construction activity.
T8	Sycamore	9	520	B2	

5.0 Tree Protection Measures

5.1 Based on the proposed layout and those trees proposed for retention, Table 3 below provides suitable protection measures/ mitigation to minimise the potential negative impacts to retained trees as stated at **4.2**.

Table 3: Potential Impacts to Retained Trees & Proposed Protection Measure / Mitigation

	<u>Potential</u> Impact	<u>Affecting</u>	<u>Protection Measure</u> / Mitigation	<u>Description / Specification and</u> <u>Procedure</u>
			Construction	Phase
1	General construction activity	H1, G4 and T8	Tree Protection Fencing	Tree Protection fencing to be erected in the locations shown to the specification provided.

5.2 On the basis of the above and the contents of this report, we do not consider the production of an Arboricultural Method Statement necessary at this stage. The erection of tree protection fencing in advance of the commencement of the development, ensuring it is retained in-situ throughout the entire construction phase, with works carried out carefully within the influencing distance of retained trees should ensure no particular adverse impact on retained trees from the proposed development.

6.0 Conclusions & Recommendations

- **6.1** The proposals to develop the site by the construction of thirty-three residential dwellings will directly require the removal of G6.
- **6.2** In the absence of suitable controls, the development also has the potential to have an indirect impact on H1, G4 and T8 that are proposed for retention as part of the development of the site.
- **6.3** Protection of retained trees from the impacts of the development proposals can be provided by:
 - The erection of protective fencing in advance of the commencement of the development in the locations shown.
- **6.4** Compensation for the impact of the development, together with landscape and biodiversity enhancements can be achieved by way of the following:
 - The planting of trees, shrubs and where applicable hedges as part of a comprehensive landscape scheme to replace any vegetation lost and to integrate the development into the wider landscape; and
 - The use of a mixture of native and ornamental species within planting schemes, where those species are suited to the site and local landscape.

7.0 References

Department for Communities and Local Government (February 2019) *National Planning Policy Framework*;

British Standard 5837: 2012 *Trees in relation to design, demolition and construction – Recommendations*;

National Joint Utilities Group publication *Guidelines for the Planning, Installation and Maintenance of Utility Apparatus in Proximity to Trees – Volume 4.*



Landscape, Arboricultural & Ecological Solutions for the Built Environment

Appendix 1

S:\Technical References & Standard Report Inserts\Appendix 1 Ascerta.doc

Site:	P.1318.2	0 Melid	en Road	, Dyserth	– Pha	ise 2	LL18	6BP	S	urveyor:		Robert Armitage			
Clier	nt: Macbryd	e Home	es									25 th January, 2018			
									Surv	ey Date:	UPD	OATED 21 st April 2020	ASC	:e	rta
Brief	Tree Sur	vey to	BS5837:	2012					0	Survey		Rainy			
									Co	nditions:			Landscape	Trees	Ecology
			-		1			_		_	-			Paç	ge 1 of 2
T.	Species	Ht (m)	Stem DBH	RPA Radius		Branc	h Spread		Ht	Age	P	Structural Condition & General Comments	Preliminary Recommendations	Est.	Cat
110			(mm)	(m)	N	S	Е	w	Clearan	01033	Condition	Ceneral Comments	(not to be actioned	(913)	Grade
				(,		-			ce (m)				without a valid planning		
													consent)		
	THE TREES, GROU							RECOR			IDER TREE S		NG AREA TO SUPPORT PHA	SE 1 OF	THE
	DEVE		I (APP REF	42/2018/092	5). AN I	IREE	NUTLI	SIEDA	RE INCLUD		PHASE 1 AN	ID ARE THEREFORE NOT IMP	ACTED BY THE PROPOSAL.		
H1	Hawthorn and Elder	3.5	120 # average	1.44	0.5	0.5	0.5	0.5	0	EM	F	Discontinuous linear feature previously maintained at 1.5m but now with vigorous new growth to 3.5m. Scrappy appearance but some retention value as individual. Stems located immediately adjacent the assumed site boundary fence. Previously poorly pruned in the past Poor pruning	Prune canopies as necessary to create a uniform maintained feature.	30	B2
T6	Sycamore	12	530	6.36	4	4	4	4	6	ЕМ	F	wounds now with vigorous new epicormic growth. Remaining canopy appears full and in good vigour. Not a particularly good example of species. Low long-term retention value.		30	C2
Т7	Cypress	6	300#	3.60	2.5	2.5	2.5	3	1.5	EM	F	Typical form for species. Stem appears to be located immediately off-site. Relatively unimportant tree.	No works required at this stage.	30	C2
G4	Ash, Sycamore and Cypress.	14	560	6.72	4	4	6.5	4	3	Y/EM	F	Self-seed Ash and Sycamore scrub. Not particularly arboriculturally important. Located immediately adjacent existing road	No works required at this stage.	30	B2/C2

NOTE: The Category Grade applied to trees surveyed is consistent with the recommendations within Table 1 of BS5837: 2012, however this does not necessarily correlate with the visual importance of a tree within the wider landscape, nor does it dictate which trees should be retained at the cost of quality development. Where trees are to be lost to accommodate a development, recommendations will be made such as to provide suitable mitigation and compensation, and to integrate the development into the wider landscape.

Key to Abbreviations & Headings

Species: Common name used

T. No.: Tree number (T = Tree, G – Group, W = Woodland, H = Hedge, Cpt. = Compartment) Stem DBH (Diameter at Breast Height): Measured at 1.5m above ground level* Ht Crown Clearance: Canopy ground clearance Structural Condition: Description of any observed defects Cat. Grade: Tree quality assessment in accordance with BS5837: 2012

Root Protection Area Radius: Root Protection Area as per BS5837: 2012 Age Class: Y = Young, EM =Early Mature, M = Mature, OM = Over mature, D = Dead Preliminary Recommendations: Made in respect of known / intended use of the site * For groups of trees, the stem diameter of the largest tree in the group is generally used # Denotes estimated DBH where access was not possible

Ht: Approximate height of tree from ground level in metres Branch Spread: Extent of canopy spread in metres to each of the four cardinal points P (Physiological) Condition: G = Good, F = Fair, P = Poor, D = Dead Est. (yrs): Estimated remaining contribution in years

\\5.193.134.43\Ascerta\All Jobs\1318.20 Meliden Road, Dyserth - Phase 2\03 Working\02 Reports\02 TREES\P.1318.20 Tree Data Table To BS 5837 2012.Docx

© Ascerta

Site:	P.1318.2	0 Melid	en Road	, Dyserth	– Pha	ise 2	LL18	6BP	S	Surveyor:		Robert Armitage			
Clier	nt: Macbryd	e Home	es									25 th January, 2018			
									Surv	ey Date:	UPD	ATED 21 st April 2020	ASC	:e	rta
Brief	Tree Sur	vey to I	BS5837:	2012						Survey		Rainy			
									Co	nditions:			Landscape	Trees	Ecology
										-			–	Paç	je 2 of 2
T. No	Species	Ht (m)	Stem DBH	RPA Radius		Branc	h Spread	1	Ht	Age Class	P	Structural Condition & General Comments	Preliminary Recommendations	Est. (vrs)	Cat
			(mm)	(m)	Ν	S	E	w	Clearan ce (m)	01033	Condition	Ceneral Comments	(not to be actioned without a valid planning consent)	(913)	Grade
Т8	Sycamore	9	520	6.24	7	7	7	7	4	ЕМ	F	Well balanced open grown form. Some retention value as an individual. Located approx. 3m from existing retaining wall. Poorly pruned in past with occluded branch wounds.	No works required at this stage.	30	B2
G5	Cherry	6	550	6.60#	5	5	3	3	3	EM/M	F	Typical form for species. Not particularly good examples of species. Branch into multiple main leaders at approx. 2m. Ornamental species. Low long-term retention value.	No works required at this stage.	20	B2/C2
H2	Hawthorn	4	180# average	2.16	1	1	1	1	0	EM	F	Well established dense boundary hedging. Multiple stems thick. Provides good dense screen. Poorly maintained in past.	No works required at this stage.	30	B2
G6	Blackthorn, Hawthorn, Sycamore, Elder and Holly	2-10	350+ 350	5.93	4	4	4	4	0	Y/EM	F	Predominantly high-density Blackthorn scrub to 3m. Occasional taller Sycamore, but not particularly good examples of species. Linear group of trees along western edge of group forms an unmaintained hedge-like feature.	Remove to accommodate the development proposals. Plant replacement trees at the landscaping stage of the project.	30	C2

NOTE: The Category Grade applied to trees surveyed is consistent with the recommendations within Table 1 of BS5837: 2012, however this does not necessarily correlate with the visual importance of a tree within the wider landscape, nor does it dictate which trees should be retained at the cost of quality development. Where trees are to be lost to accommodate a development, recommendations will be made such as to provide suitable mitigation and compensation, and to integrate the development into the wider landscape.

Key to Abbreviations & Headings

T. No.: Tree number (T = Tree, G – Group, W = Woodland, H = Hedge, Cpt. = Compartment) Stem DBH (Diameter at Breast Height): Measured at 1.5m above ground level* Ht Crown Clearance: Canopy ground clearance Structural Condition: Description of any observed defects Cat. Grade: Tree quality assessment in accordance with BS5837: 2012

Species: Common name used

Root Protection Area Radius: Root Protection Area as per BS5837: 2012 Age Class: Y = Young, EM =Early Mature, M = Mature, OM = Over mature, D = Dead Preliminary Recommendations: Made in respect of known / intended use of the site * For groups of trees, the stem diameter of the largest tree in the group is generally used # Denotes estimated DBH where access was not possible

Ht: Approximate height of tree from ground level in metres Branch Spread: Extent of canopy spread in metres to each of the four cardinal points P (Physiological) Condition: G = Good, F = Fair, P = Poor, D = Dead Est. (yrs): Estimated remaining contribution in years

\\5.193.134.43\Ascerta\All Jobs\1318.20 Meliden Road, Dyserth - Phase 2\03 Working\02 Reports\02 TREES\P.1318.20 Tree Data Table To BS 5837 2012.Docx



Landscape, Arboricultural & Ecological Solutions for the Built Environment

Appendix 2

S:\Technical References & Standard Report Inserts\Appendix 2 Ascerta.doc





	KEV	·
[Existing tree to be retained
	•	
		Extent of Root Protection Area retained trees in accordance v BS5837: 2012 Trees in relation
l	/	design, demolition a construction - Recommendatior
	++++++++	Proposed location of protect fencing - see inset for type construction detail
3S58	337:2012 re 3 Examples of ab	iove-ground stabilizing systems
BS58 Figur	337:2012 re 3 Examples of ab	ove-ground stabilizing systems
BS55 Figur	337:2012 re 3 Examples of ab	eve-ground stabilizing systems
BS58 Figur	337:2012 re 3 Examples of ab	eve-ground stabilizing systems
BS58 Figur	ablizer strut with bas	eve-ground stabilizing systems
a) SI Sigur	abilizer strut mountee	ove-ground stabilizing systems
a) Si	abilizer strut mountee	
а) SI Sigur	abilizer strut with base abilizer strut with base abilizer strut mounter Abilizer strut mounter Abilizer strut mounter Abilizer strut mounter Abilizer strut mounter	
a) Si	abilizer strut with base abilizer strut with base abilizer strut with abilities and abilities ab	eve-ground stabilizing systems
a) SI	abilizer strut with base abilizer strut with base abilizer strut with base abilizer strut mounter abilizer strut m	
a) SI	abilizer strut with base abilizer strut with base abilizer strut with base abilizer strut mounter abilizer strut m	eve-ground stabilizing systems The system of the systems a plate secured with ground pins The system of the sys
assess igur a) SI SI SI SI SI SI SI SI SI SI SI SI SI S	abilizer strut with base abilizer strut with base abilizer strut with base abilizer strut mounter abilizer strut m	eve-ground stabilizing systems The system of the systems are plate secured with ground pirs The system of the system Scape Trees Ecology t: 0845 463 4405 Dandscape trees ecology.com andscape trees ecology.com