

with spades or small machinery. A second site inspection should then take place to ensure that the

14 Tree species selected subject to soil conditions and NHBC guidance. Root barriers may be

required subject to findings from soil analysis and engineer's details.

soil is fit for purpose.

LEGEND

Existing Trees to be Retained




.



Trees to be planted as 18-20 cm in key locations (site boundaries) to provide an instant impact, Semi-mature, 4.5-6m high with 2m clear stem. Trees to be secured with stakes. Trees to have an irrigation pipe wrapped around the rootball for manual watering. Otherwise, trees to be planted as 14-16cm girth, Extra Heavy Standard, 3.5-4m high. Trees to be staked and secured with suitable rubber ties.




Proposed Medium Size Ornamental Trees
Trees to be planted as 14-16cm girth, Extra Heavy
Standard, 3.5-4m high. Trees to be staked and
secured with suitable rubber ties.




containers, 2-3m high and secured with single stake and suitable rubber ties.

Proposed Formal Evergreen Hedge



Proposed Native Hedgerow
Proposed native hedge to be 80-100cm height
planted in a double staggered row at 300mm
centers. To have minimum 5 species. Spiral Guards



to protect plants.

containers at 3-5 p/m², and enhanced by feature specimens in 10-20L pots.

Proposed Native Shrubs Mix

To be planted as bare root stock, 60-80cm, planted

at 2/m2. **Proposed Woodland Mix**To be planted at 1/m2.

To be planted at 1/m2.


Proposed Wildflower Meadow
To be Dual Purpose Wildflower Seeds LWXP 100%,
supplied by Landlife Wildflowers or similar
approved. Including annual flowering wildflower mix
for instant first year effect (including cornflower and

Proposed Grass Areas
POS areas to be rich-species grassland.
Front gardens to be turfed.
Back gardens to client specification.

Planting Note please see drawing 204

Planting Schedule please see drawing 201

LOCATION MAP



REVISION NOTES			
Rev	Ву	Description	Date
G	RN	Updated in line with latest layout	17.07.25
F	RN	Planting beds removed from plots 1-3; hedgerows removed from road edge	01.04.25
Ε	RN	Updated in line with latest layout	31.03.25
D	TS	Updated in line with latest layout	07.02.24
С	TS	Updated in line with latest layout	13.11.24

Client
Castle Green Homes

istic dicentifolite

ject

Quarry Farm, Oakenholt

B EO Updated in line with latest layout

A AJ Updated in line with latest layout

Description

Status

commencing. IF IN DOUBT PLEASE ASK.

British Standards and Code of Practice.

manufacturer's instructions and details.

7. All work and materials are to be in accordance with the relevant

8. All Proprietary products are to be used strictly in accordance with the

Planting Plan(4 of 4)

For Approve

Scale @ A1 Draw

1:250 FZ KP
Job number Drawing number
4441 204

G Revision

02.05.24

24.04.24

30.08.23

Chartered landscape architects
address: 4th Floor Studio 10 Little Lever St Manchester M1 1HR

tel: 0161 235 0600 fax 0601 email info@tpmlandscape.co.uk

Checked