Do not scale this drawing (printed or electronic version).

Contractors must check all dimensions from site

This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.

All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.

Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when comparedto the original paper or electronic image.

Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.

Notes:-



KEY

Site Red Line Boundary

Public Right of Way (PRoW)

Sewer Easement

Proposed Garden Fencing
Timber fencing designed to allow passage of hedgehogs Erinaceus europaeus.

Soft Works

Existing Tree
To be retained.

Existing Vegetation
To be retained and enhanced.

Existing Vegetation
To be removed.

Proposed Focal Point Tree Planting

Proposed Tree Planting

Proposed Hedge Planting

Proposed Welcome Feature Planting
Ornamental shrub mix to welcome into site.

Proposed Ornamental Shrub Planting
Ornamental shrub mix.

Proposed Mixed Native Scrub Planting

Proposed Seasonal Bulb Planting
Native bulb mix.

Proposed Marginals Mix

Proposed Wet Meadow Mix
Wet meadow seed mix
WFG9 Wetland and Pond Areas by Germinal Amenity

Proposed Seeded Species Rich Lawn
WFG20 by Germinal Amenity

Proposed Mown Strip

Proposed Turf Grass

Plant Schedule

QTY	UNIT	CODE	PLANTNAME	STOCK	FORM	GIRTH/HEIGHT
Trees						
4	No.	ACE CAM ss	Acer campestre	B	STD	10-12cm
1	No.	BET PEN ms4	Betula pendula (Multi-Stem)		RB	
11	No.	CAR FRA hs	Carpinus betulus "Frans Fontaine"	RB	STD	12-14cm
3	No.	CRA STR ss	Crataegus monogyna "Stricta"	RB	STD	10-12cm
6	No.	LIQ SLS xhs	Liquidambar styraciflua 'Slender Silhouette	RB	STD	14-16cm
4	No.	MAL STR hs	Malus baccata 'Street Parade'	RB	STD	12-14cm
4	No.	MAL SYL ss	Malus sylvestris	B	STD	10-12cm
11	No.	PHO RED ss	Photinia fraserii 'Red Robin'	RB	STD	10-12cm
4	No.	PRU PLE ss	Prunus avium "Plena"	RB	STD	10-12cm
1	No.	PRU AVI ss	Prunus avium	B	STD	10-12cm
3	No.	PYR CHA ss	Pyrus calleryana "Chanticleer"	B	STD	10-12cm
3	No.	QUE ROB ss	Quercus robur	B	STD	10-12cm
1	No.	QUE RUB xhs	Quercus rubra	RB	STD	14-16cm
2	No.	SAL B	Salix babylonica	RB	STD	14-16cm
4	No.	SOR AUC ss	Sorbus aucuparia	B	STD	10-12cm

QTY	UNIT	CODE	PLANTNAME	STOCK	SIZE
Hedges					
68	m	Ela ebb Hedge	Elaeagnus x ebbingei	C3L	30-40cm
204	No.	Plants spaced @3/m in a Single Row			
20	m	Gris lit Hedge 5L	Griselinia littoralis	C5L	60-80cm
80	No.	Plants spaced @4/m in a Double Staggered Row			
44	m	Lav Hid Hedge	Lavandula augustifolia "HidCote"	C3L	20-30cm
176	No.	Plants spaced @4/m in a Single Row			
207	m	Pru lus Hedge (3L)	Prunus lusitanica	C3L	40-60cm
1035	No.	Plants spaced @5/m in a Single Row			
178	m	Ver Hedge	Veronica 'Mrs Winder'	C3L	40-60cm
890	No.	Plants spaced @5/m in a Single Row			
99	m	Ver var Hedge	Veronica x franciscana 'Variegata'	C3L	40-60cm
495	No.	Plants spaced @5/m in a Single Row			

PERCENT	QTY	UNIT	PLANTNAME	STOCK	SIZE
Plant Mixes					
69m2 BULB MIX 4 planted @20/m2					
33%	455	No.	Galanthus nivalis	5-6cm	
33%	455	No.	Crocus vernus	5/+cm	
34%	469	No.	Narcissus pseudonarcissus	10-12cm	
Individual varieties to be planted in groups of approximately 7.					
693m2 NATIVE SCRUB MIX CYMRAEG planted @1m centres					
30%	208	No.	Crataegus monogyna	B Trans	40-60cm
20%	139	No.	Salix caprea	B Trans	40-60cm
15%	104	No.	Sambucus nigra	B Trans	60-80cm
25%	173	No.	Corylus avellana	C3L	40-60cm
10%	69	No.	Rosa canina	C3L	40-60cm
Individual varieties to be planted in groups of approximately 3-5.					
17m2 SS Mix A planted @4/m2					
25%	17	No.	Aucuba japonica 'Variegata'	C5L	40-60cm
25%	17	No.	Escallonia 'Iveyi'	C5L	30-50cm
35%	24	No.	Euonymus japonicus 'Bravo'	C5L	50-70cm
15%	10	No.	Vinca minor 'Illumination'	C2L	10-20cm
20m2 SS Mix B planted @4/m2					
25%	20	No.	Choisya ternate	C5L	40-60cm
25%	20	No.	Pittosporum tenuifolium 'Variegatum'	C5L	40-60cm
35%	28	No.	Viburnum tinus 'Eve Price'	C5L	40-50cm
15%	12	No.	Vinca minor	C2L	10-20cm
168m2 POLLEN AND NECTAR WILDFLOWER MIX planted @1/m2					
100%	168	No.	No. Superior Pollen and Nectar Wildflower Seed Mix	Seed	
Seeded at 2g m2 over prepared ground from Habitat Aid					
1303m2 WET MEADOW MIX planted @1/m2					
100%	1303	No.	No. Wet Wildflower Meadow Seed Mix	Seed	
Seeded at 4g m2 over prepared ground from Habitat Aid					
493m2 MARGINALS MIX 2 planted @4/m2					
10%	197	No.	Carex riparia	C0.5L	
15%	296	No.	Caltha palustris	C0.5L	
15%	296	No.	Lythrum salicaria	C0.5L	
25%	493	No.	Luzula sylvatica	C0.5L	
20%	394	No.	Iris pseudoacorus	C0.5L	
15%	296	No.	Alisma plantago-aquatica	C0.5L	
Individual varieties to be planted in groups of 7.					

Notes and Abbreviations

B	=	Bare root (bagged).
C	=	Container (or pot) grown, followed by size of the container (or pot).
FORM	=	Shape of tree as supplied by the nursery.
QTY	=	Quantity
RB	=	Rootballed (balled and wrapped).
SIZE	=	Height or Spread of juvenile plant.
Std	=	(clear stem) Standard.
STOCK	=	Root condition/protection method eg Bare root.
Trans	=	Transplant (or undercut seedling).

- Refer to specification for further information.
- All plants to be completely hardened off
- Substitutions to be agreed with Landscape Architect.

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P02	05/11/26	Updated following comments	JP	SW
P01	29/10/26	First issue	JP	SW

Client:	Project:	Drawn:	Checked:	Approved:	Date:
CASTLE GREEN HOMES	BRYN DERW, ABERGELE	JP	SW	SA	05/11/26

Issue:	Title:	Dwg No:	Scale @ A1:	Revision:
PLANNING	PLANTING PLAN	UG_3419_LAN_SL_DRW_301	1:500	P02

URBAN GREEN

A: Ground Floor, The Tower, Deva City Office Park, Trinity Way, Manchester M3 7BF

T: +44 (0) 161 312 3131

weareurbangreen.co.uk